

# PURCHASE REQUEST

Pursuant to LRA BAC-PGSM No. 2024-098

Entity Name: LAND REGISTRATION AUTHORITY

Fund Cluster: \_\_\_\_\_

Office/Section:		PR No.: 00322025 Responsibility Center Code: _____			Date: February 13, 2025	
Stock / Property No.	Unit	Item Description	Quantity	Unit Cost	Total Cost	
	lot	Supply and Installation of New Generator Set For LRA Central Office	1	2,168,000.00	2,168,000.00	
	set	<u>Main Requirement Specifications:</u> <b>333 kVA Generator Set</b> Standby Power 1800 rpm, Three Phase, 230V Silent Type w/ enclosure. Genset must be equipped with mufflers, MCCB, Battery Trickle Charger, Batteries, Battery Cables, Gauges (Line Voltage Output, Frequency, RPM, Oil Pressure, Temperature, Power Factor, Running Hours) Alarm & Shutdown Protection (Low Oil Pressure, High Temp, Low/High Voltage, Under/ Over RPM & Frequency; Emergency Button, Built-in Fuel Base Tank.	1			
	units	<b>Exhaust fans (Industrial type) 1 Intel 1 Outlet</b> Exhaust Fan Assembled Fully Assembled Diameter 16 in Blade Material Polypropylene Drive Type Direct Drive Exhaust Airflow@ 0.000 in SP 2 970 cfm For Cut-Out Height 17 12 in For Cut-Out Width 17 7/16 in For Minimum Wall Thickness 3/4 in Frame Material Fiberglass Guard Finish Powder Coated Guard Material Steel Guard Type Intake Housing Material Aluminum Includes Intake Guard Includes Dehumidistat No Maximum Airflow 2	1			
	set	<b>Exhaust Pipes</b> Black Iron/ Galvanized Iron Pipe schedule 40 or any approved equal; Heavy duty dampens vibration; To minimize back pressure from bends in the exhaust system, make sweeping 90 degree bends with radii of at least one and one half times the pipe diameter	1			
	set	<b>Ducting</b> Typical Indoor Ventilation Duct	1			
					<b>2,168,000.00</b>	
Purpose:		For the use of the Central Office, this Authority.				
Signature :		Requested by:		Approved by:		
Printed Name:		ROBERT PAUL REMEGIO T. ANCHETA		GERARDO PANGA SIRIOS		
Designation :		Chief, Property & Supply Section		Administrator		